

Job Information

Job #:	94773				Date:	October 16, 2018
Priority:	_	Authorized OT:	No	Authorized by:		

Customer Information

Name:	Name: Saint Jean			Reason:	
Contact:		Motor#:		PO#:	
Application:	_	Special notes:			

Name Plate Information

Manufacturer:	SACCARDO	Enclosure :	Totally Enclosed Fan Cooled
Serial#:	160762	Model#:	02ED31GS02
Service Factor:		Frame:	
Horsepower/kW:	5.9	Rated RPM:	2850
Rated Amps:	22.3/12	Rated Voltage:	230/460
Phase:	3	Cycles:	50
Special design:	No		

Enclosure Type image



Nameplate

DE

ODE

F1

F2





Тор

WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301









Mechanical Inspection

Inspect bolt holes and fasteners. Validate correct fasteners.

Does the shaft turn freely?:	Yes	Contaminant(s):	None
Shaft rotation:	Bi-directional	Contaminant(s) Amt:	None
Shaft grounding device present?:	No		
Type of grounding device:			

Shaft runout(TIR-Inbound):

Bearings DE:	Worn	Bearings DE make:	FAG
Insulated:	No	Bearing DE Size:	6208 2RS
Bearings ODE:	Worn	Bearings ODE make:	FAG
Bearing Type:	Ball	Bearing ODE Size:	6305 2RS
Bearings Retainer:	Yes	Thermal Protection:	Yes
Retainer condition:	_	Thermal Protection Type:	_

Bearing Type Image



Bearing Make Image



Bearing Retainer Image



Thermal Protection



WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Mechanical Inspection (Continued)

Lubrication Type:	Grease	Thermal Protection device DE:	N/A
Lubrication brand inbound:	Mobile Polyrex EM	Thermal Protection device ODE:	N/A
Lubrication brand outbound:	Mobile Polyrex EM		
Grease Amt DE:	Full	Grease Cond. DE:	New
Grease Amt ODE:	Full	Grease Cond. ODE:	New
Seals DE type:	Isolators	Seals Image:	
Seals DE size:	40 60 10		00
Seals DE (inbound) condition :	Bad		200
		Seals Image 2:	
Seals ODE type:	Isolators	Could Image 2.	
Seals ODE size:	25 47 7		
Seals ODE (inbound) condition :	Bad		
Shaft damage cause:	None	Shaft Image:	



WEST TENNESSE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Mechanical Inspection (Continued)

Brg. Image: Bushings/sleeves image: Not Available Water jacket: Ok Fan: Ok Frame cond.: Good Not Available Motor Mount Position: Horizontal/Foot mount Endbell type: Single piece Missing parts? Endbell Image: J-Box cover O-rings J-Box HH cover None Glands



WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301

Other missing parts



Mechanical Inspection (Continued)

Air Gap Meaurements (N/A on Single Piec	Does Air Gap Meet Customer or EASA spec(<10% variation)?	
DE @ 0	ODE @ 0	_
DE @ 90	ODE @ 90	
DE @ 180	ODE @ 180	
DE @ 270	ODE @ 270	


AC Electrical Inspection

Number of leads:	6	Terminal Markings:	UVW	
Length of leads:		REF: NEMA Stds Markings Identifie	s. MG 1-2009, Rev. 1- ed By Color:	-2010, 2.41-Terminal
Size of leads:		1-Blue 2-White 3-Orange	5-Black 6-No color assigned 7-No color assigned	P1-No color assigned P2-Brown
Lead condition:	Good	4-Yellow	8-Red	
Lug type:		Connections As Rec	ceived: High voltage	9
Lug Condition:	Good	т	erminal	Lugs
Lug size:				
Lug Attachment:	_			

WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



AC Electrical Inspection (Continued)



WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



AC Electrical Inspection (Continued)

Winding color:	Like new	Winding	image W	/inding Thermal Protection	n: Yes	
Winding condition :	Solid					
Winding Thermal Protection DE:						
Winding Thermal Protection ODE:						
Stator test results:	Salvageable					
Megs incoming: 0	Good	Surge incoming:	Good	Hi-pot incoming:	Good	
Winding Resistance I	ncoming					
Pha	ses A to B	Phases B to C	Phases (C to A Resistive	imbalance	
Incoming 1.4	86	1.486	1.486	0.0		
Leads/jum	oers: Ok					
If other, leads/jum	pers:					

Mechanical Inspection

Inspect bolt holes and fasteners. Validate correct fasteners.

Shaft Condition:	Good	Bearings Retainer:	Yes
Type of grounding device:		Bearing DE Size:	6208 2RS
Shaft runout(TIR-Inbound):		Bearing ODE Size:	6305 2RS

Retainer condition:

WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301 CENTRAL ARKANSAS 6812 Lindsey Rd. Little Rock, AR 72206 Phone 501-375-9178 Fax 501-375-4254



Mechanical Inspection (Continued)

Seals DE condition :	Worn	Brg. Seats DE:	Good	
Seals DE type:	Isolators	If DE undersized, amt.:		
Seals DE size:	40 60 10	Brg. Seats ODE:	Good	
Seals DE (inbound) condition :	Bad	If ODE undersized, amt.:		
Seals ODE condition :	Worn	Shaft damage:	ОК	
Seals ODE type:	Isolators			
Seals ODE size:	25 47 7	Bushings/sleeves DE:	Ok	
Seals ODE (inbound) condition :	Bad	Bushings/sleeves ODE:	Ok	
Endbell fits/damage:	Good	Foot/Flange condition:	Ok	
Endbell DE size:	3.1510 Bad	Foot flatness:	Pass	
Endbell DE insulated?:	No	Does Air Gap Meet Cus	stomer or EASA spec(<10%	
Endbell ODE size:	2.4410 Good	variation)?		
Endbell ODE insulated?:	No	_		

VEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Conclusion

Component Failure

Cause of Failure

Comments

Seals and bearings DE HOUSING FITS BAD FOUND METAL FATIGUE And CONTAMINATION

Service Tech name:

Robert Wiley

Service Tech signature:

Aur Wiley

WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300

Fax 901-873-5301