

Job Information

Job #:	96983				Date:	June 23, 2020
Priority:	_	Authorized OT:	No	Authorized by:		

Customer Information

Name:	Kimberly Clark		Reason:	
Contact:		Motor#:		PO#:
Application:	_	Special notes:		

Name Plate Information

Manufacturer:	Baldor	Enclosure :	Totally Enclosed Fan Cooled	E
Serial#:	A1311062087	Model#:		
Service Factor:	1.15	Frame:	365TS	
Horsepower/kW:	75	Rated RPM:	3555	
Rated Amps:	161/80.7	Rated Voltage:	230/460	
Phase:	3	Cycles:	60	
Special design:	No			

Enclosure Type image



Nameplate

DE

ODE

F1

F2

Тор







WEST TENNESSE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Mechanical Inspection

Inspect bolt holes and fasteners. Validate correct fasteners.

Does the shaft turn freely?:	No	Contaminant(s):	Oil
Shaft rotation:	Bi-directional	Contaminant(s) Amt:	Cup
Shaft grounding device present?:	No	Contaminant Image:	1 AL
Type of grounding device:			
Shaft runout(TIR-Inbound):			

Bearings DE:	Worn	Bearings DE make:	Koyo
Insulated:	No	Bearing DE Size:	6313
Bearings ODE:	Locked up	Bearings ODE make:	Коуо
Bearing Type:	Ball	Bearing ODE Size:	6313
Bearings Retainer:	Yes	Thermal Protection:	No
Retainer condition:	Good	Thermal Protection Type:	_

Bearing Type Image



Bearing Make Image



WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301

CENTRAL ARKANSAS 6812 Lindsey Rd. Little Rock, AR 72206 Phone 501-375-9178 Fax 501-375-4254



Bearing Retainer Image



Thermal Protection



Mechanical Inspection (Continued)

Lubrication Type:	Grease	Thermal Protection device DE:	_
Lubrication brand inbound:	Unknown	Thermal Protection device ODE:	_
Lubrication brand outbound:	Unknown		
Grease Amt DE:	Full	Grease Cond. DE:	Hard
Grease Amt ODE:	Full	Grease Cond. ODE:	Hard
Seals DE type:	N/A		
Seals DE size:			
Seals DE (inbound) condition :			
Seals ODE type:	N/A		
Seals ODE size:			
Seals ODE (inbound) condition			
Shaft damage cause:	None	Shaft Image:	



VEST TENNESSE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Mechanical Inspection (Continued)

Brg. Image:



Water jacket:	N/A		Fan:	Broken	Frame co	ond.:	Good
Motor Mount Posit	tion: Horizontal/F	oot mount			Endbell type:	Singl	e piece
Missing parts?)			Endbell Image:			
J-Box cover	O-rings	🗌 J-Box			EON		663
HH cover	Glands	Vone					
Other missing pa	rts						

VEST TENNESSE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Mechanical Inspection (Continued)

Air Gap Meaurements (N/A on Single Pie	Does Air Gap Meet Customer or EASA spec(<10% variation)?	
DE @ 0	ODE @ 0	_
DE @ 90	ODE @ 90	
DE @ 180	ODE @ 180	
DE @ 270	ODE @ 270	


AC Electrical Inspection

Number of leads:	9	Terminal Markings:					
Length of leads:	15in	REF: NEMA Stds. MG 1-2009, Rev. 1-2010, 2.41-Terminal Markings Identified By Color:					
Size of leads:		1-Blue 2-White 3-Orange	5-Black 6-No color assigned 7-No color assigned	P1-No color assigned P2-Brown			
Lead condition:	Good	4-Yellow	8-Red				
Lug type:		Connections As Re	eceived:				
Lug Condition:	_		Terminal	Lugs			
Lug size:							
Lug Attachment:	_						

WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



AC Electrical Inspection (Continued)



WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



AC Electrical Inspection (Continued)

Winding color:	Still has color	Winding	g image	Winding The	rmal Protectio	on: No
Winding condition :	Solid			2		
Winding Thermal Protection DE:	_					
Winding Thermal Protection ODE:	_	3				
Stator test results:	Salvageable					
Megs incoming: Go	bod	Surge incoming:	Good	Hi-po	ot incoming:	Good
Winding Resistance In	coming					
Phas	es A to B	Phases B to C	Phase	es C to A	Resistive	e imbalance
Incoming 0.00		0.00	0.00			
Leads/jump	ers: Ok		Lea	d jumper Imag	je. :	
If other, leads/jump	ers:					
Mechanical Ins	pection					
Inspect bolt holes and fa	asteners. Valida	te correct fasteners.				
Shaft Cond	dition: Good		Bearing	gs Retainer:	Yes	
Type of grounding de	evice:		Bearin	ng DE Size:	6313	

Bearing ODE Size:

6313

Shaft runout(TIR-Inbound):

7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301

Retainer condition:

Good



Mechanical Inspection (Continued)

Seals DE condition :	None	Brg. Seats DE:	Good
Seals DE type:	N/A	If DE undersized, amt.:	
Seals DE size:		Brg. Seats ODE:	Good
Seals DE (inbound) condition :		If ODE undersized, amt.:	
Seals ODE condition :	None	Shaft damage:	ОК
Seals ODE type:	N/A		
Seals ODE size:		Bushings/sleeves DE:	Ok
Seals ODE (inbound) condition :		Bushings/sleeves ODE:	Ok
Endbell fits/damage:	Good	Foot/Flange condition:	Ok
Endbell DE size:	5.5127GOOD	Foot flatness:	Pass
Endbell DE insulated?:	_		tomer or EASA spec(<10%
Endbell ODE size:	5.5143 BAD	variation)?	
Endbell ODE insulated?:	_		

VEST TENNESSE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301



Conclusion

Component Failure

Bearings, bearing fits on ODE

Cause of Failure

Grease contamination ODE bearing locked up

Comments

Recommend reconditioning, new bearings, and machine work

Service Tech name: Chr

Chris Wiley

Service Tech signature:

(hur alility

WEST TENNESSEE 7030 Ryburn Drive Millington, TN 38053 Phone 901-873-5300 Fax 901-873-5301